DRAWING CCAG-2-21-33-1

DRAWING CCAG-2-21-33-3

Remove post
Re-install existing Bus Lane sign beneath new 30 sign on lamp column

Extend existing post.
Re-install existing Bus Lane sign beneath new 30 sign.
Re-install existing No Through Road sign beneath new 20 sign.

Install signs above CPZ signs

Remove 20 & 30 signs from LC and retain for re-use.

Remove post and retain signs for re-use

N

NOTES

LEGEND

- 1 — 20mph signs 300mm dia. to diag. 670 to be mounted **back to back** on lamp column as Appendix12/1 TS1
- 2 — 20mph & 30mph Zone signs to be mounted back to back on lamp column as Appendix12/1 TS2
- 3 — 20mph & 30mph Zone signs to be mounted back to back on new post as Appendix12/1 TS3
- 4 — 20mph & 30mph signs to be mounted back to back on lamp column as Appendix12/1 TS4
- 5 — 20mph & 30mph signs to be mounted back to back on new post as Appendix12/1 TS5
- 6 — Signs to be mounted as Appendix12/1, TS number as shown on plan
- Extent of new 20mph restrictions

© Crown Copyright and database right 2011. Ordnance Survey 100019747.

REVISIONS

No.	Date	Notes	Int.	Ckd.

Title

CCAG2
20 mph limits
2018/19
Southern area - signage
Eaton area

Scale(s) NTS

Date	DWG. No.
Designed by PW	CCAG2-21-33-2/7
Drawn By PW	NEG. No.
Checked By LA	

Andy Watt
Head of City Development Services
City Hall, Norwich, NR2 1NH
tel 0344 980 3333
highways@norwich.gov.uk